

7-20-9W

KANSAS WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
Union National Bank Bldg, Wichita, Kansas.

THE TEXAS COMPANY.
W.D. McFarland No. 2

SEC. 7 T. 20 R. 9W.
NW SE SW
330' NL 1129' EL.

Total Depth. 3344
Comm. 4-30-34 Comp. 6- 7-34
Shot or Treated. 100 qts 3260-3285
Contractor. Campbell-Parker.
Issued. 7-14-34.

County. Rice.

JUL 14 1934



Rotary
CASING.

Elevation.

12 $\frac{1}{8}$ " 152' 8 $\frac{1}{4}$ " 3300'

Production. DRY

Figures Indicate Bottom of Formations.

surface clay	48
sand	105
shale and shells	260
shale and shells grey med	575
shale and shells red	650
shale and shells blue	1040
shale and salt blue	1159
shale and shells	1259
salt	1350
shale and shells grey	1525
lime white	1592
broken lime and shale white	1710
shale grey med	1750
lime grey hard	1760
broken lime & shale	1780
shale and shells grey	1880
broken lime grey	1910
broken lime	1960
shale and shells blue	2038
shale and shells	2092
broken lime grey med	3207
lime	3218
shale	3232
lime	3246

shale	3258
shale brown	3268
sand and shale green	3297
lime grey	3344 TD.

Cored and reamed 3258 to 3344.

Top of Lansing. 2960
Simpson 3268 to 3297
Siliceous lime 3297 to 3344

Acidized through 8 $\frac{1}{4}$ " casing. No increase.
shot with 100 qts 3260-3285. Small show
of oil and water.