


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - THE DRILLERS GAS COMPANY  
Farm - Gray No. 1

SEC. 1 T. 20 R. 9W  
CSE NW

Total Depth. 3001'  
Comm. 3-3-47 Comp. 3-31-47  
Shot or Treated. Acid.  
Contractor. Springer & Harper  
Issued. 4-19-47

County. Rice KANSAS



Elevation. \_\_\_\_\_

Production. 270,000 gas & 2 BWPH

CASING:

8-5/8" 147' Cem. w/ 75 sx  
5-1/2" OD 2930' Cem. w/275 sx

Figures Indicate Bottom of Formations.  
Rip csg. 2003-2006  
1000 gal. acid.  
Gauge 270,000 cu.ft. Gas  
2 bbls. wtr per hour.

soil	0-6
clay	30
sand	40
shale	110
sand	120
sand & shale	153
red rock	205
red rock & shale	285
shale & shells	733
shale	790
salt	1095
shale & lime	1170
lime	1205
lime & shale brks	1315
lime	1420
lime & shale	1790
lime brkn & shale	1940
lime & shale	2010
shale & shells	2115
lime	2145
lime & shale	2550
lime & shale brks	2635
lime	2750
lime & shale	2850
shale	2866
lime	2877
sand	2884
shale	2899
lime	2946
lime brkn	2960
shale & lime	2974
lime gy	2979
lime & shale	2991
lime brwn	2996
lime	3001
Total Depth	

Tops:

Foraker	1905
Amerius	1968
Tarkio	2123
Douglas	2750
Dodge	2865
Kansas City	2899

Slight show oil at 2979  
L.W. plug 2900  
91 shots 2865-2884  
500 gal. acid-Gauge 112,000 cu.ft.  
20 qts. 2865-2884. No increase gas.  
L.W. plug 2220  
22 shots 2125-2134. No shows.  
1000 gal. acid. Slight show gas.  
L. W. plug 2030  
49 shots 1968-1983. No shows  
19 shots 2004-2009 1/2. Est. 1 1/2 million  
gas.