

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company- HERMAN GEO. KAISER

Farm- Speck

No. 1

SEC. 3 T. 20 R. 9W

NW NE NW

100' W of NW NE NW

Total Depth. 3262'

Comm. 5-23-56

Shot or Treated.

Contractor.

Issued. 1-5-57

Comp. 6-8-56

County Rice

KANSAS



Elevation. 1682' RB

Production. Dry

CASING:

8" 224'

NO LOG AVAILABLE.

Development Well.

Figures Indicate Bottom of Formations.

shale, gry & grn, red-maroon. Some limestone, fine crystalline.	2810	lime, chalky in part; some sub-oolitic limestone, limestone, chalky, fine crystalline. Some fine crystalline limestone, sub-oolitic, unbleached.	2945	shale as above. Some brwn-gry, crystalline, fossiliferous, mottled limestone, sub-oolitic in part, dense	3045
shale, gry grn, lumpy. Some gry, micaceous siltstone	2820	Increase in shale, gry & drk olive grn. Limestone as above.	2950	limestone, tan-gry, sub-oolitic, w/some gry oolites, unleached, dense	3050
shale, gry & d. grn	2830	limestone, chalky. Shale, grn	2955	Sand as above w/increase in shale, gry & grn.	3055
shale as above. Few pieces tan-brwn, fine crystalline, flaky, mottled limestone	2840	limestone, oolitic & oolitic porosity. Very slight tr. stain. Abundance of porosity without stain	2960	limestone, oolitic & oolitic.	3060
limestone, tan-brwn-gry, fine crystalline, flaky, dirty & mottled appearing	2850	Same as above. Good oolitic porosity. No shows.	2970	limestone, fine crystalline, chalky	2975
Limestone as above. Some gry, fine-medium grained sandstone, clean w/some micaceous inclusions. Fair stain in few pieces.	2860	limestone, fine crystalline, limestone, chalky, some fine crystalline, limestone	2980	limestone, oolitic, slightly oolitic; some gry, oolitic limestone, unleached.	3065
limestone, w/some gry oolites. Few pieces chert	2870	Same as above	2985	Increase in shale, gry & grn.	3070
limestone, fine crystalline gry, crystalline limestone	2880	Same w/some light gry-brwn limestone	2990	Same as above. Some chalky limestone	3075
limestone, crystalline, chalky, some fine crystalline w/gry oolites.	2890	Same w/increase in shale, gry limestone, tan-brwn, dense, lithographic. Shale, gry & dk. grn. Some chalky limestone.	3000	Same as above. Some gry, fine crystalline, dense, tight limestone.	3080
Some limestone as above	2900	limestone, gry-tan-brwn, fine crystalline, Shale, gry & grn	3005	Increase in shale, gry grn & red.	3085
limestone, chalky; some gry, fine crystalline, limestone	2910	limestone, fine crystalline, chalky. Some limestone as above	3010	shale, gry & grn. Some tan, fine crystalline limestone.	3090
limestone as above, some oolitic & slightly fossiliferous limestone, tight. Limestone, fine crystalline, dense & tight.	2920	Slight increase in shale, gry & grn. Some limestone, chalky; some tan-light gry. fine crystalline, limestone.	3015	Some gry, medium crystalline limestone	3095
limestone, mealy, sub-oolitic, w/poor vugular porosity. Some speckle cherts. Shale, gry-grn	2930	Same as above w/some blk. carbonaceous shale	3020	limestone, fine crystalline, sub-oolitic, w/some poor oolitic porosity w/very slight tr of spotted tarry blk oil stain.	3100
limestone, w/oolites, shale, gry & grn. Some gry cherts.	2940	limestone, chalky, some gry, fine crystalline. Shale as above	3025	limestone, tan-brwn, crystalline; some tan-gry, fine crystalline limestone, Shale gry & grn	3105
Large increase in shale, gry & grn.	2950	limestone, sub-oolitic, unbleached. Shale, gry & grn. Some tan-brwn, fossiliferous limestone	3030	limestone as above. Some dense, lithographic, limestone.	3110
Some gry, fine crystalline limestone	2960	Increase in shale, gry, red & maroon. Limestone, tan-brwn, fine crystalline	3035		
limestone, medium-fine crystalline, oolitic, w/dk. gry oolites,	2970		3040		
Same as above w/some buff tan, fine crystalline limestone	2980				
limestone, fine crystal-	2990				

(OVER)

Sec. 3 T. 20 R. 9W
Company Herman Geo. Kaiser
Farm Speck No. 1

Same as above	3115	Same as above	3214
limestone, tan, fine crystalline, some brwn mottled limestone	3120	Circ. shales, cherts-sandstone as above	3214
Same as above	3125	Same as above	3220
limestone, fine crystalline, chalky; some medium crystalline, limestone; some tan, lithographic limestone	3130	cherts, oolitic in part. Dolomite, tan-brwn., fine medium crystalline, No porosity. No shows	3225
Same as above	3135	Same as above	3233
Same w/abundance white, chalky limestone	3140	Circ. Dolomite, tan-brwn., fine-medium crystalline, dense & tight. Poor porosity. No shows. Fair odor.	3233
Increase shale, gry, limestone as above.	3145	Circ. Dolomite, tan-cream, fine-medium crystalline, sucrosic in part; some medium crystalline dolomite w/fair vugular & inter-crystalline porosity. Some light staining. Some free oil. Fair odor.	3238
Some L. gry, fine crystalline limestone	3150	Circ. Abundance of shale & shaly dolomite. Some weathered appearing dolomite. Some tan, dense dolomite as above	3243
limestone, chalky. Some fine crystalline limestone	3155	Sand shale & shaly, weathered dolomite as above	3250
Increase shale, gry, dk. grn., some blk.	3160	Dolomite, tan-cream, fine crystalline, dense. Shale, drk grn & olive grn.	3255
Some brwn, medium crystalline limestone	3165	Same.	3260
Same as above. Some brwn cherts. Some gry. & brwn, fine crystalline limestone.	3170	Circ. Dolomite, fine crystalline. Some vugular porosity. No shows. Some shale as above	3262
Abundance shale, gry, dk. olive grn, red & maroon, some brwn.	3175	Total Depth RTD.	
Shale as above w/some gry-tan & brwn., medium crystalline limestone	3180	TOPS:	
Increase in limestone, some brwn, fine medium crystalline.	3185	Anhydrite (scout)	1145
Same w/some pinkish Marmaton limestone.	3190	Heebner (scout)	2705
Shale, red, maroon, gry & grn.	3195	Brwn lime	2834
limestone, white-tan-pink-brwn., medium-fine crystalline. Abundance of shale	3200	Lansing	2860
Abundance of shale as above. Some red, pink, cream, tan cherts; some oolitic cherts.	3208	B/Kansas City	3186
Shale, gry, dk, grn., maroon & red. Same cherts as above	3214	Conglomerate	3186
light grn., sdy, slightly waxy shale	3214	Arbuckle	3226
Sand cherts as above. Some sdy shales. Few clusters of medium grained, rounded sandstone, Some shale, drk. gry & drk grn	3214		
shale, gry & drk grn.	3214		
Some sandstone as above. Some wh., tripolitic cherts	3214		
Increase in cherts, red, pink, yellow & cream; some oolitic cherts. Shale as above	3214		
Circ. Same as above. Some sdy. shales; some slightly waxy, olive grn. & maroon shales.	3214		