


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

AUTO-ORDNANCE CORPORATION.
Peterson No. 2

SEC. 4 T. 20 R. 9 W.
CE $\frac{1}{2}$ SE NW

Total Depth. 3267
Comm. 4-14-42 Comp. 5-19-42
Shot or Treated.
Contractor, Mercury Drilling Co.
Issued. 8-8-42

County Rice.



CASING.

85/8" 210' cemented.
5 1/2" 3267' cemented.

Elevation.

Production DRY

Figures Indicate Bottom of Formations

surface soil and sand	46
sand	170
shale and shells	210
red bed	292
anhydrite	318
shale and shells	830
salt and lime shells	980
salt and shale	1070
broken lime	1305
shy lime	1410
shale and shells	1503
broken lime	1770
shale	1805
shale and shells	1900
shale and lime streaks	2016
shale and shells	2365
broken lime	2419
lime and shale	2460
lime	2495
shale and shells	2514
shale	2534
shale and shells	2571
lime	2821
shale	2868
lime	2900
lime & shale strks	2975
lime	3187
lime and shale & chert	3225
conglomerate	3233
chert	3235
conglomerate	3263 1/2
Arbuckle lime	3267

Total Depth.