

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg. Wichita, Kansas

Company C. U. BAY
Farm Coffman No. 1.

SEC. 5 T. 20 R. 9 W
S E c SW

Total Depth. 3263'
Comm. 8-25-46 Comp. 9-26-46
Shot or Treated.
Contractor. Gebbert & Lindas
issued. 10-19-46

County. Rice
KANSAS



Elevation. _____

Production. Dry

CASING:

8 5/8" 212'
5 1/2" 3248'

Figures Indicate Bottom of Formations.

surface	0-20
clay	40
sand	60
clay	150
red bed & shells	207
red bed	320
anhydrite	342
red bed & shale	635
red bed, shale & shells	1055
shale & shells	1300
shale gy & lime	1360
sand & shale	1390
sand, shale, red bed	1395
sand & lime	1460
lime	1520
lime brkn	1620
shale & lime	1830
lime brkn & shale	2035
lime & shale	2165
lime brkn	2270
lime & shale	2390
lime brkn	2575
lime	3200
lime & shale	3229
lime	3251
lime	3263
Total Depth.	

Testing Inf:

RTD 3249: 5 1/2" 3248

DD 3263 T.D. 500 Acid HF

SCO 3257-59, Inc. 3261-62

Perf. 3090-96, SCO, 500 A.
HF

Perf. 30/3080-88 Swb 2

gal. oil & 5 B"/hr. Squeeze

Perf. 30/2992-98 2 gal. oil
& 1 B"/hr

D & A 9-26-46

Tops: Anhydrite	320
Br. Lans.	2876
Wh. Lans.	2895
Conglomerate	3211
Simpson	3233
Arbuckle	3248