


OHIO OIL CO.
B.G. Proffitt No. 10.

SEC. 5 T. 20 R. 9W
NE NW NE NW
880' fr EL 330' fr NL NW $\frac{1}{4}$

Total Depth. 3244' P.B. 3240
Comm. 4-26-37 Comp. 6-11-37
Shot or Treated. 1000 & 1000 Gals.
Contractor.
Issued. 8-7-37

County. Rice



CASING:
20" 191' 6 5/8" 3228'
15 1/2" 600'
12 1/2" 1525'
10" 2223'
8 5/8" 2910'

Elevation.

Figures Indicate Bottom of Formations. Production. Pot. 295 B.

sand wtr	190	shale	1870	lime	3185
red rock	315	sdv lime	1880	var. col. shale	3195
lime	330	2 BW 1870-80		shale & lime	3205
red rock	445	lime	1915	lime	3242
shale	490	shale	1940	sand	3244
red rock	610	lime	1950	Total Depth.	
shale	680	shale	1970		
red rock	695	lime	1975		
shale	715	shale	1995	Plugged back 3240	
shale red	720	lime	2000		
shale	815	shale	2085	Acidized with 1000 Gals.	
salt	1080	red rock	2095	Acid Pump 79 B. 24 hrs.	
shale	1085	shale	2140	Reacidized with 1000 gals.	
salt	1135	lime	2150	Acid Pump 295 B. 24 hrs.	
shale	1170	shale	2170		
shale shells	1190	sand	2200		
shale	1200	6 BW 2180-2200			
lime	1215	shale	2212		
shale shells	1250	lime	2223		
shale red	1260	lime	2230		
lime	1265	shale	2245		
shale	1275	lime	2260		
lime	1300	shale	2295		
shale	1310	lime	2305		
lime	1320	shale	2325		
shale	1330	lime	2395		
lime	1365	shale	2405		
red rock	1375	lime	2435		
shale red	1380	shale	2450		
lime	1420	sdv lime	2470		
shale wtr 1500-05	1430	2 BW 2450-70			
lime	1527	lime	2635		
shale	1530	2 BW 2635-45			
red rock	1540	lime sdv	2645		
lime	1550	lime	2770		
shale	1575	red rock	2778		
lime	1590	shale	2785		
shale	1600	lime	2790		
lime	1610	shale	2872		
shale	1620	lime	2878		
red rock	1625	shale	2890		
lime	1640	lime	2910		
shale	1645	shale	2915		
shale red	1660	lime	2930		
shale	1695	shale shells	2940		
lime	1700	lime	2950		
shale	1705	shale	2960		
lime	1735	lime	3075		
shale	1755	$\frac{1}{2}$ BW 2980-90			
red rock	1765	shale	3085		
lime	1810	lime	3090		
rod rock	1815	shale	3100		
shale	1830	lime	3170		
lime	1840	shale	3175		