

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company - OHIO OIL COMPANY
Farm - B. G. Proffitt No. 12

SEC. 5 T. 20 R. 9W
SE NE NW
330' fr E1 & 990' fr N1 NW $\frac{1}{4}$

Total Depth. 3226'
Comm. 11-2-48 Comp. 12-11-40
Shot or Treated.
Contractor.
Issued. 1-29-49

County. Rice

KANSAS



Elevation. _____

Production. 50 Bbls.

CASING:

10-3/4" 224.56' Cem. W/125 Sx.
7" 3243'6" Cem. W/ 200 Sx.

Figures Indicate Bottom of Formations.

collar & sub base	8
surface soil & sand	30
sand	190
sand shells	200
shells & red rock	300
lime & shells	495
shale & shells	970
shale & lime	1530
lime	1605
lime & shale	2140
lime	2775
lime & shale	2835
shale & lime	2885
shale	2908
lime	3150
lime & shale	3195
lime	3222
arbutckle RTD	3224
arbutckle	3226
Total Depth	

Top Arbutckle 3222K.B. (3220 DF)
RTD 3224 KB (3222 DF)
Bot 7" 3223 KB (3221 DF)
El. 1719 Datum - Top Arbutckle
- 1503 KB (-1501 DF)

only 1 - 24-hr test taken, 25 90
& 103 BF.

Tops:
Hoobner shale 2763
Brn. Lime 2885
Hensing 2899
arbutckle 3224

DST 2982-3002 open 60 mins.
Rec. 20 ft. mud, fair odor, no oil.