

GYPSY OIL COMPANY.
Christopher No. 3.

SEC. 6 T. 20 R. 9 W.
SE NE NE

Total Depth. 3244.
Comm. 2-12-34 Comp. 4-11-34
Shot or Treated.
Contractor.
Issued. 4-28-34.

County. Rice.

CASING.

20"	203'	10"	2329'
15 $\frac{1}{2}$ "	325'	8 $\frac{1}{2}$ "	2926'
12 $\frac{1}{2}$ "	1562'	6 $\frac{5}{8}$ "	3239'



Elevation.

Figures Indicate Bottom of Formstions.
Production. Potential Pump
1555 B. Oil 24 Hours.

sand	70	lime	1810	shale	2895
clay	80	red rock	1820	lime	3080
shale HFW 74	90	lime	1835	shale	3085
shale	100	shale	1845	lime	3195
gyp	105	lime	1852	shale	3200
clay	175	shale	1870	lime	3212
sdv shale	200	red rock	1880	SAMPLE LOG.	
HFW 225-235. 2 BW 245-255		shale	1890	shale red& grey	3219
red rock	320	lime	1910	lime with thin shale	
gyp	325	2 $\frac{1}{2}$ BW 1890-1905		beds	3229
lime	340	red rock	1915	conglomerate	3233
red rock	625	shale blue	1925	sdv shale green	3238
shale	685	lime	1940	sand	3239
red rock	720	shale	1945	dolomite	3244
shale	755	lime	1952	F.D.	
lime	760	shale	1960		
shale	840	lime	1980	Hole filled 1000' with	
salt	1105	shale	2010	water in 1 hour at 3244.	
shale	1110	lime	2020	and 2800' with oil in	
shale and salt	1140	shale	2035	3 $\frac{1}{2}$ hours.	
salt	1155	shale and shells	2060		
shale	1240	shale	2080	4-12-34 Swab 351 B.Oil	
shale and shells	1275	lime	2090	in 6 hours swabbing from	
red rock	1285	shale	2135	900' off bottom,	
shale	1295	shale	2170		
lime	1315	lime	2180	4-17-34. Pump 1555 B.Oil	
shale	1340	shale	2220	and no water for a 24H.	
lime	1355	sand	2235	Potential test.	
shale	1360	HFW 2220-35			
lime	1370	shale	2238		
broken lime	1375	shale	2240		
shale	1390	shale	2245		
red rock	1405	lime	2270		
lime	1420	shale	2305		
broken lime	1450	shale	2315		
2 BW 1430-1440		shale	2320		
shale	1455	shale	2325		
lime	1520	shale	2330		
sand	1540	lime	2365		
shale	1560	shale	2400		
lime	1590	lime	2405		
red rock	1600	lime	2430		
sdv lime	1615	lime	2440		
shale	1630	shale	2450		
lime	1635	lime	2460		
shale	1640	sdv shale	2490		
red rock	1645	sand	2500		
shale	1665	1 BW 2490-2500			
lime	1675	lime	2560		
red rock	1680	lime	2605		
shale	1695	shale	2610		
red rock	1710	lime	2775		
lime	1750	shale	2785		
shale	1780	lime	2800		
red rock	1790	red rock	2810		
lime	1795	lime	2815		