

KANSAS WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
 Union National Bank Bldg, Wichita, Kansas.

GYPSY OIL COMPANY.
 Christopher No. 4.


SEC. 6 T. 20 R 9W.
 NEc NW NE

Total Depth. 3233.
 Comm. 5-8-34 Comp. 6-4-34.
 Shot or Treated.
 Contractor.
 Issued. 9-15-34.

County. Rice.

CASING.

12 $\frac{1}{2}$ " 215' 65/8" liner at 3227'
 8 $\frac{1}{2}$ " 3203'



Elevation.

Production. Potential
 1605 B.

Figures Indicate Bottom of Formations.

red rock	287	lime	2781
broken lime	320	shale	2802
shale and shells	587	lime and shale	2892
red rock	650	lime	2900
shale and shells	790	lime	2903
shale	845	lime and shale	2927
salt	1081	lime	3103
salt and shale	1120	shale and shells	3128
broken lime	1131	lime and shale	3188
shale and shells	1150	SAMPLE LOG.	
red rock	1180	lime	3203
shale and lime shells	1310	Test standardized at 3203	
lime shells	1323	shale red	3208
lime	1364	lime and red shale	3222
shale	1414	sdv shale	3226
lime	1424	dolomite	3233
shale and shells	1478	T.D.	
shale	1534		
lime	1560	show oil 3227	
shale and shells	1580	Pay 3229-3230. Filled 600' with oil 1 Hr.	
lime and shale	1640	Pay 3231-3233 Filled from 600'-2900' with	
lime and shale	1660	oil in 2 hours.	
shale	1680	6-4-34 Swabbed 975 bbls oil 13 $\frac{1}{2}$ hours	
shale and shells	1793	Swabbing. 1400' off bottom.	
shale	1850	6-9-34. Pumped 1605 B. Oil & no wtr in	
lime	1900	24 hours. State Potential Test.	
shale and shells	1950		
shale	2000		
shale and lime	2090		
lime and shale	2180		
shale and shells	2337		
lime	2345		
shale	2360		
lime and shale	2395		
shale & shells	2473		
shale	2478		
lime	2512		
shale	2542		
lime	2577		
broken lime	2627		
lime	2707		
broken lime	2774		