


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
Union National Bank Bldg, Wichita, Kansas

EMPIRE OIL AND REFINING CO.
Profitt No. 6

SEC. 6 T. 20 R. 9W.
NE SW SE
990' N & 1650' W of SE cor.

Total Depth. 3262
Comm. 4-8-35 Comp. 4-30-35.
Shot or Treated. 950 gal acid.
Contractor. J.E. Mabey.
Issued. 6-8-35.

County. Rice.



CASING.

15 1/2" 165' 65/8" 63'7" liner set at 3254 Elevation.
8 1/2" 3245'

Figures Indicate Bottom of Formations. Production. Potential 812 B. :
in 24 Hr. after
acid.

red bed and sand	85	broken lime	2813
sand and shale	150	lime	2818
sand hard	198	broken lime	2835
shale and shells	850	sdv shale	2895
salt	1100	lime and shale	3010
broken lime and shale	1178	lime and shale broken	3062
lime and shale	1264	broken lime	3093
shale and shells	1328	lime and shale	3123
shale and lime	1513	broken lime	3155
lime shells	1573	shale and lime	3201
lime	1580	lime	3228
shale	1608	lime and shale	3239
shale and lime	1656	SIM correction 3239 = 3254	
shale and shells	1715	slate green Corr. Meas. 3248 = 3256	
broken lime & shale	1800	shale green & sand	3257
shale and shells	1972	show oil 3254.	
lime and shale	2033	S.L.M. corr. 3257 = 3254.	
lime and broken shale	2088	lime	3262
shale and shells	2170	Total Depth.	
lime	2190		
shale and shells	2235	Top of Siliceous lime Corr. 3254	
lime	2265		
lime broken	2300		
lime	2354		
lime broken	2378		
lime and shale	2443		
broken lime	2500		
lime hard	2548		
lime	2630		
shale and shells	2640		
shale and lime	2683		
lime	2708		