

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
Union National Bk Bldg, Wichita, Kansas.,

LARIC OIL & GAS CO.
Footc No. 4

SEC. 7 T. 20S R. 9W.
SE SW NE

Total Depth. 3280'
Comm. 2-3-36. Comp. 3-10-36.
Shot or Treated.
Contractor. Broadwater Drilling Co.
Issued. 3-28-36.

County. Rice

CASING.
12 1/2" 160'
6 5/8" 3250'



Elevation.

Production. Pot. 1116 Bbls.

Figures Indicate Bottom of Formations.

clay	30	standardized	
sand	50	show of oil	3268
sandy red shale	150	dolomite	3275
shale	190	1000 gal. acid.	
shale & shells	330	dolomite	3280
shale & lime	450	1000 gal. acid	
shale & shells	600	Total Depth	
shale & shells	830	Potential 1116 bbl. oil in 21 hours.	
shale	850		
salt	1075		
lime & broken shale	1195		
lime	1330		
broken lime & shale	1385		
lime	1552		
broken lime & shale	1652		
lime	1680		
broken lime	1845		
shale & shells	1897		
shale	2008		
shale & shells	2217		
shale	2232		
shale & shells	2422		
lime & shale	2482		
broken shale & lime	2537		
lime	2699		
broken lime	2740		
lime & shale	2770		
broken lime	2840		
shale	2861		
shale & shells	2919		
shale	2964		
broken lime	3016		
lime	3143		
lime	3246		
conglomerate	3250		
dolomite	3253		