


SACO OIL CO.
A.R. Foote No. 1-B.

SEC. 7 T. 20 R. 9W.
NEo SE

Total Depth. 3308
Comm. 6-27-38 Comp. 9-2-38
Shot or Treated. 380 gal.
Contractor. Saco Oil Co.
Issued. 11-12-38

County Rice.



CASING.

15 1/2" 144'6"
12 1/2" 790'
10" 1821'10"
8 3/4" 2404' UR 2764'3"
6 5/8" 3273'

Elevation.

Production Pot. 20 B.

Figures Indicate Bottom of Formations.

| | | | | | |
|--------------------|------|------------------------|------|---------------------------|------|
| clay and sand | 40 | lime | 1770 | shale | 2830 |
| clay yellow | 145 | slate | 1775 | red rock | 2835 |
| slate blue | 155 | lime broken | 1785 | shale | 2880 |
| shale red | 170 | lime hard | 1790 | shaly shale | 2890 |
| red rock | 210 | shale light | 1800 | shale | 2930 |
| lime | 220 | red rock | 1805 | lime | 3025 |
| red rock | 225 | lime | 1807 | lime broken | 3030 |
| lime | 240 | red rock | 1810 | lime | 3095 |
| red rock | 325 | lime | 1820 | slate | 3100 |
| shale red | 357 | lime broken | 1835 | lime | 3145 |
| lime | 377 | shale & shells | 1850 | shale | 3150 |
| slate grey | 380 | shale | 1860 | lime | 3170 |
| slate red | 385 | lime | 1875 | red rock | 3175 |
| red rock | 465 | slate and shells | 1885 | lime | 3259 |
| shale grey | 500 | red rock | 1892 | conglomerate | 3272 |
| slate red | 550 | lime | 1925 | Top Siliceous | |
| red rock | 595 | slate | 1930 | lime | 3273 |
| slate and red rock | 655 | lime | 1955 | lime hard | 3276 |
| shale grey | 720 | slate | 1960 | Br lime Oil | 3282 |
| red rock | 735 | shale | 1965 | lime | 3286 |
| slate blue | 760 | lime and shells | 1975 | H.SLM 3291 | |
| red rock | 770 | shale | 2035 | lime | 3299 |
| slate blue | 835 | lime broken | 2045 | lime sat. | 3301 |
| shale blue | 877 | shale | 2050 | cherty dolomite | 3304 |
| salt | 1145 | lime | 2070 | lime sat. | 3306 |
| salt and shale | 1155 | red rock | 2080 | cherty dolomite | 3308 |
| slate | 1160 | slate | 2105 | Total Depth. | |
| salt and lime | 1180 | lime hard | 2115 | WATER. | |
| slate | 1210 | shale dark | 2125 | 2 BWPHR 170-210 | |
| lime and shale | 1240 | red rock | 2130 | 2 BWPHR 1450-1460 | |
| red rock | 1245 | shale | 2190 | 4 BWPHR 1555-1565 | |
| lime | 1257 | lime | 2220 | 2 BWPHR 1915 | |
| red rock | 1267 | slate | 2255 | 3 BWPHR 2375-2390 | |
| lime | 1277 | lime | 2300 | HFV 2495-2517 | |
| shale light | 1295 | slate | 2303 | 5 BFWH 2650-2680 | |
| red rock | 1300 | lime | 2315 | 2 Sect. PH 3030 | |
| lime | 1325 | slate | 2330 | show oil & some gas | |
| shale and shells | 1360 | lime | 2355 | 3025-3030 | |
| lime broken | 1395 | slate | 2370 | small sh oil 3273 | |
| slate blue | 1405 | sand dark | 2390 | 1/2 B.O.PH 3282 | |
| red rock | 1415 | slate | 2414 | with no water showing | |
| lime | 1450 | lime | 2435 | Hole filled 300' in 12 | |
| slate white | 1460 | slate | 2440 | hours 8:30 P.M. to | |
| lime | 1485 | lime | 2450 | 8:30 AM and bailed one | |
| slate | 1490 | shale brown and shells | 2485 | sec. bailer wtr. | |
| lime sdy | 1565 | slate | 2490 | 8-27-38 3308 hole filled | |
| lime hard | 1575 | sand | 2515 | 845' 1 SB wtr 12 hours. | |
| red rock | 1580 | lime sdy | 2517 | 8-28-38 standing 32 | |
| lime | 1620 | lime | 2540 | hours 1700' fluid with | |
| slate | 1630 | slate | 2545 | 2 SB wtr. | |
| lime | 1645 | lime | 2575 | Following acid treatment | |
| slate | 1655 | slate | 2579 | at 3308. well went on wtr | |
| lime | 1665 | lime | 2648 | after pumping 50 bbls. | |
| red rock | 1675 | shaly lime | 2680 | | |
| lime | 1680 | lime | 2715 | 380 gal acid. | |
| slate blue | 1685 | lime sdy | 2732 | | |
| red rock | 1695 | lime | 2807 | | |
| lime | 1710 | shale | 2810 | | |
| shale | 1720 | lime | 2825 | | |