


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.

SACO OIL CO.
Wickerham No. 1-A.

SEC. 7 T. 20 R. 9W
NE SW SE

Total Depth. 3387'
Com. 7-30-37 Comp. 12-21-37
Shot or Treated.
Contractor. Saco Oil Co.
Issued. 1-8-38

County. Rice



CASING:
15 1/2" 154' 8 1/4" 2548'
12 1/2" 870' 7" 2696' UR 2800'
10 " 1825' 5 3/16" 3340'
Plugged back to gas sand &
Run 104 Jts 53/16 2240 cemented to top
Pulled 50 Jts 53/16 1050 gas sand

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

slate	40	lime	1675	shale	2850
wtr sand	150	red rock	1685	red rock	2855
slate	175	lime	1695	shale	2950
red rock	230	red rock	1700	slate	2970
wtr sand	245	shale blue	1705	K.C. lime	3000
red rock	280	red rock	1710	lime	3165
sand red rock	320	shale blue	1715	slate	3170
lime	340	lime	1730	lime	3235
red rock	360	red rock	1750	shale drk	3240
lime	380	shale	1790	lime	3250
red rock	390	lime	1815	redrock	3255
slate blue	400	red rock	1855	lime	3301
red rock	420	shale & lime	1880	slate	3308
lime	435	slate	1895	red rock	3315
red rock	460	slate blue	1930	lime	3330
slate white	505	sdv lime	1965	shale green	3335
red rock	585	slate drk	2000	lime <i>Oil.</i>	3340
slate brown	605	lime	2002	sdv lime	3355
red rock	650	slate	2050	lime & grey shale	3370
slate white	720	lime	2060	lime <i>Oil.</i> HFW 3387	3387
red rock	735	slate blue	2070	Total Depth.	
shale blue	830	lime	2080		
slate white	875	shale blue	2095	Oil & Gas show	
shale blue	885	red rock	2105	gas sand 2250-2275	
lime	890	slate	2155	10 Gals. Oil per hr for 3	
salt	910	shale	2170	hours 3055-3068 K.C. lime	
slate	912	lime & shale	2200		
salt	920	slate	2250	Water Record	
salt & lime	925	gas sand	2275		
salt	1030	slate	2288	HFW 140	
lime & salt	1040	lime	2300	4 BWPH 230-45	
salt	1153	shale	2320 2330	8 BWPH 430-45	
slate blue	1160	shale & shells	2345	8 BWPH 1560-70	
slate	1205	slate	2405	1 BWPH 1930-40	
red rock	1210	sdv lime	2425	2 BWPH 2410-20	
slate	1220	lime	2435	HFW 2540	
lime & shale	1240	shale	2445	Hole flowing wtr 2615	
lime	1270	lime	2455	HFW 3387 T.D.	
slate	1275	shale	2460		
lime	1280	lime	2465		
slate wh	1310	shale	2480		
red rock	1320	lime	2503		
shale	1340	slate	2535		
sdv lime	1360	lime	2635		
red rock	1370	shale	2645		
lime	1430	lime	2650		
red rock	1447	shale grey	2655		
lime	1485	lime	2725		
slate	1500	shale	2750		
sand & lime	1550	lime	2755		
sdv shale	1565	shale drk	2760		
lime	1595	lime	2785		
red rock	1600	slate	2790		
slate	1620	lime	2820		
lime	1625	shale drk	2825		
slate	1670	shale grey	2848		

*Con. By Bureau
1/15/38*