


SACO OIL CO.  
Wickerham No. 3A.

SEC. 7 T. 20 R. 9W  
SE SW SE

Total Depth. 3310'  
Comm. 9-2-37 Comp. 9-24-37  
Shot or Treated. 1000 Gals.  
Contractor. Triangle Drlg. Co.  
Issued. 10-23-37

County. Rice



CASING:  
10" 187'2"

Elevation.

Production. Pot. 938 B.

Figures Indicate Bottom of Formations.

surface clay - sand	95
shale & shells	870
shale	890
salt	1095
shale-salt shells	1165
shale-lime shells	1365
lime-shale break	1435
lime	1465
sdv lime	1495
sdv lime - shale	1565
sdv lime white	1585
lime & shale	1705
brkn lime	1760
lime & shale	1965
shale & lime shells	2060
lime & shale	2285
lime	2405
lime & shale	2445
brkn lime	2550
Topeka lime	2635
lime	2685
shale & sdv lime	2715
lime-shale	2820
lime brkn	2905
lime & shale	2990
Kansas City lime	3125
lime	3210
lime & shale	3293
lime	3307
Siliceous lime	3310
Total Depth.	