


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
 Union National Bk Bldg., Wichita, Kansas.

SINCLAIR PRAIRIE OIL CO.
 Chas. O. Sharpe No. 5.

SEC. 7 T. 20 R.9W
 NE c NE
 330' fr N & EL
 N $\frac{1}{2}$ NE $\frac{1}{4}$

Total Depth. 3262 $\frac{1}{2}$ '
 Comm. 4-16-36. Comp. 5-8-36
 Shot or Treated. 1000 gals. Acid.
 Contractor. ---
 Issued. 7-11-36

County. Rice.



Casing:
 12 $\frac{1}{2}$ " 163'
 7 " 3241'
 2 $\frac{1}{2}$ " tubing.

Elevation.

Production. Pot. 406
 Oil, 100 wtr.

Figures Indicate Bottom of Formations.

surface	20
shale & clay	156
shale & lime	164
shale & shells	775
shale & salt	1200
shale & shells	1275
shale & lime	1377
shale & shells	1548
shale & lime	1975
shale	2010
shale & lime	2060
shale	2125
shale & shells	2170
lime	2190
shale	2255
lime broken	2330
lime & shale	2400
lime	2447
broken lime	2507
lime	2673
lime hard	2750
lime & shale	2760
lime	2808
shale & lime	2940
Kansas City lime	2988
lime	3050
shale & lime	3246
Top Arbuckle	3242
lime arbuckle	3262 $\frac{1}{2}$
Total Depth	

Potential Production 406 B. Oil, 100 water after
 1000 Gals. Acid.