

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas


Company- BENNETT & ROBERTS DRILLING CO.
Farm- Coldwater No. 1

SEC. 8 T. 20 R. 9W
C N/2 NW SW

Total Depth. 3266
Comm. 10-1-55 Comp. 10-16-55

County Rice KANSAS

Shot or Treated.
Contractor. Bennett & Roberts Drilling Co.
Issued. 12-3-55



CASING:
8 5/8 @ 219' w/ 135 sx cmt.
5 1/2 @ 3253.5' w/ 75 sx cmt.

Elevation. 1738 DF

Production. 25 BOPD

Figures indicate Bottom of Formations.

sand	70
sand rock & shale	150
soft blue shale	185
red bed	345
shale & shells	400
anhydrite	435
shale, shells & red bed	912
salt & shale	1130
lime & shale	2944
lime	3254
lime	3266
Total Depth	

RTD

TOPS:

Cimarron anhydrite	400
Heebner	2779
Toronto	2797
Douglas	2812
Brown lime	2907
Lansing-KC	2930
Base K. C.	3203
Conglomerate shale	3223
Arbuckle	3253

All RB Meas.

No electric logs run

DST #1: 3025-34, open 1 hr. wk. bl.
15 min. flushed tool after 30 min.
rec. 35' drlg. mud, trace oil specks
w/ slight odor, BHP 245#/20 min.