

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bk Bldg., Wichita, Kansas.


MAGNOLIA PETRO. CO.  
C. O. Sharpe No. 1.

SEC. '8 T. 20 R.9W  
NW SW NW

Total Depth. 3308' P.B. 3280'  
Comm. 6-21-36 Comp. 8-21-36  
Shot or Treated.  
Contractor.  
Issued. 9-26-36

County. Rice

CASING:  
12 $\frac{1}{2}$ " 206'  
7 " 3258'



Elevation.

Production. Dry.

Figures Indicate Bottom of Formations.

cellar	8
clay	40
sand	65
shale & shells	206
shale blue	320
red bed	450
shale & shells	1050
salt	1200
shale & shells	1365
lime	1405
lime & shale	1565
lime	1670
shale	1880
shale & shells	2435
lime	2465
shale	2510
lime	2545
shale	2560
lime	2595
shale	2600
shale & lime	2780
lime	2829
lime & shale	3060
lime	3100
shale	3135
shale & lime	3255
cored	3259
Top of Arbuckle	3257
reamed	3258
Standardized	
Arbuckle	3308
Total Depth.	

Plugged Back 3280

Well treated with 1000 Gals. Acid & 140 B. Oil on 7-14-36 at 3281  
Shot with 9 qts from 3265-3295 and with 17 qts from 3265-3295

24-36

Well drilled to 3308 Plugged back to 3300 and treated with 2000 Gals.  
Acid & 142 B. Oil 7-26-36

Well Plugged Back to 3280 and treated with 1000 Gals. Acid. & 144  
Bbls. Oil 8-14-36.