


PHILLIPS PETRO.CO.
R.P.Proffitt No. 2.

SEC.8 T.20 R.9 W
CSE NE

Total Depth. 3260'
Comm. 6-11-42 Comp. 7-22-42
Shot or Treated.
Contractor.
Issued. 8-22-42

County. Rice



CASING:
8 5/8" 246' Cem.
5 1/2" 3246' Cem.

Elevation.

Production. Pot.174 B.Pmp

Figures Indicate Bottom of Formations.

sand, gravel, shells	200
shale & lime shells	250
red bed	580
shale gy & shells	870
shale, salt, shells	1170
shale, shells, salt	1350
shale & lime	1565
lime & shale strks	1655
lime & shale	1950
shale & lime	2331
shale & brkn lime	2480
lime & shale	2665
lime	2773
lime w/shale strks	2948
lime & shale strks	3004
lime	3198
shale	3210
shale & lime	3249
lime	3250
lime	3260
Total Depth.	

Tops:
L.K.C. 2929
Arbuckle 3245½

5½" csg at 3246 Cem.
Fair porosity & sat.in
samples
Cored 3251-55, made 33 gal.OPH
Cored 3255-55½, had SO & por.
Treated w/500 Acid thru csg,
made 7.2 BOPH, no wtr
Cored 3255½-57, 75% rec. of
hrd dolo. 1st ft por.& sat.
bal.no por. or sat.
Cored 3257-60 rec 2' dense
dolo. w/few strks sat. &
spotted por.
Still making 7.2 BOPH, no wtr

Potential 174 Bbls pmp