

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - SKELLY OIL CO.
Farm - C. O. Sharpe No. 3.

SEC. 8 T. 20 R. 9 W
SE NE NW
330' FEL 330' FSL N $\frac{1}{2}$ NW $\frac{1}{4}$

Total Depth. 3275

Comm. 9-3-44

Comp. 9-27-44

Shot or Treated.

Contractor. Bodine Drlg. Co.

Issued. 2-3-45

Rotary O-3238
Cable 3238-3275

County. Rice
KANSAS



CASING:

8 5/8"

215' Cem.

5 1/2"

3235' Cem.

Elevation. _____

Production. Pot. 53 BO
23 BW, 16H.

Figures Indicate Bottom of Formations.

surface soil	10	Tops:	
clay & sand	40	Lansing	2920
sand	150	Arbuckle	3234
red bed	225		
red bed & shells	585	Stained	3234-3238
shale & shells	980		
salt & shells	1150	Rainbow show of oil-shut	
shale & shells	1250	down 12 hrs, then tested	
lime & shale	1510	5 gals free oil & no wtr	
lime sdv	1575	3249-53	
lime & shale	1635	Sli. por. & sat	3265-3269
lime	1720	Little por. & sat	3269-3275
lime & shale	1820		
shale & shells	1875	Sli. por & sat. Tested 5 gals	
lime & shale	2070	oil & no wtr. Tested 12 hrs,	
shale	2165	hole filled 225' w/ oil.	
shale & shells	2220	Ran 2" tubing & treated w/	
lime	2260	500 gals. 3235-69 9-23-44	
lime & shale	2390		
shale	2480	After acid treatment, ran	
lime & shale	2540	rods & POB 3 hrs, 16 $\frac{1}{2}$ BO	
lime	2765	& no wtr. 9-25-44 POB 8 hrs,	
lime brkn	2810	1st 4 hrs pmpd 27 $\frac{1}{2}$ BO &	
shale	2855	9 $\frac{1}{2}$ BW, 2nd 4 hrs pmpd 1 BO & 10BW.	
lime & shale	2950	On Sept. 26 POB 5 Hrs., 1BO & 31	
lime	3050	BW, then pulled rods & tubing	
lime & shale	3070		
lime	3100	9-28-44 Swbd 16 hrs, 30 BO	
lime & shale	3215	& 10 BW. Ran tubing & rods	
shale	3225	& POB 13 hrs, 47 BO & 26 BW	
shale red, lime sdv			
& chert	3234	9-29-44 POB 16 hrs, 53 BO &	
dolomite med sft		23 BW & well pmpd off	
coarsely xlyn	3236		
dolomite med hrd gy			
coarsely xlyn	3238		
dolomite hrd gy no por-			
osity or sat	3239	Pred. before shot 5 gals Oil,	
dolomite hrd gy with		no wtr. after shot POB 16 hrs	
little green shale		53 BO & 23 BW	
no por or sat	3243		
dolomite hrd gy & brown			
xlyn w/ little green			
shale no por or sat	3249		
dolomite brown & gy	3253		
dolomite brown & gy no			
por or sat	3257		
dolomite brown no por			
or sat	3263		
dolomite brown	3265		
dolomite brown & gy	3269		
dolomite brown little			
por & sat, 2000 fluid in			
hole in 16 hrs.	3275		
Total Depth			