


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - BAY PETROLEUM CORP.
Farm Dewitt No. 3.

SEC. 9 T. 20 R. 9 W
NE NW SE

Total Depth. 3247
Comm. 10-26-45 Comp. 12-12-45
Shot or Treated.
Contractor.
Issued. 3-30-46

County. Rice
KANSAS



CASING:
8 5/8" 164'
5" 3234'

Elevation. _____

Production. Est. 100 B

Figures Indicate Bottom of Formations.

sand & shells	0-164
sand & red bed	273
shale & shells	295
anhydrite	330
shale & shells	848
salt	1048
shell & shale	1175
anhydrite	1210
shale & lime	1490
cherty lime	1515
shale & lime	1615
lime	1687
shale & lime	1970
shale	2021
shale & lime	2216
lime	2270
shale	2370
shale & lime	2487
lime	2587
lime & shale	2625
lime Rotary	3241
dolomite	3247
Total Depth	

Tops:

Anhydrite	295
Lansing	2913
Conglomerate	3227
Arbuckle	3236

RTD 3240
CTD 3247
SSO 3238-40
1 BOPH 3246-47
500 Acid
1 - 5 BOPH
Est. 100 BOPD
T.D. 3247