


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company C. U. BAY
Farm DeWitt "A" No. 3

SEC. 9 T. 20 R. 9 W
NW NE SE

Total Depth. 3268'
Comm. 11-26-45 Comp. 1-5-46
Shot or Treated.
Contractor.
Issued. 3-30-46

County. Rice
KANSAS



CASING:

8" 195'
5 1/2" 3248'

Rotary 0-3248'
Cable 3248-68'

Elevation. _____

Production. Est. 50 B.

Figures Indicate Bottom of Formations.

clay	0-195
red rock	308
anhydrite	335
shale	525
shale & shells	851
salt	1066
shale & shells	1172
anhydrite	1180
lime	1282
lime & shale	1490
cherty lime	1513
lime	1518
lime & shale	2072
shale	2218
lime	2293
lime & shale	2539
lime	2609
lime cherty	2638
lime	2801
lime & shale	2907
lime	3248
T.D. w/Rotary	
dolomite	3268
Total Depth (cable)	

Tops:

Anhydrite	308
Brown Lansing	2887
Lansing	2906
Conglomerate	3237
Arbuckle	3247

Testing Record:

Bailed 10 GOFH 3261'
DD 3264' Swab 1 1/2 BOPH
TD 3268' Swab 3 BOPH