


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - BAY PETRO. CORP.
Farm DeWitt "A" No. 4

SEC. 9 T. 20 R. 9 W
NW SE SE

Total Depth. 3266
Comm. 11-29-45 Comp. 3-4-46
Shot or Treated.
Contractor. Ferrell-Young Dlg. Co.
issued. 3-23-46

County. Rice
KANSAS



CASING:
8 5/8" 225' Cem.
5 1/2" 3252' Cem.

Elevation. _____

Production. 30 to 35 BOPD
plus 25 to 30 BWPD

Figures Indicate Bottom of Formations.

cellar	4
shale, sand & shells	222
red bed & shale	315
anhydrite	650
shale & shells	1150
lime brkn	1200
lime	1635
lime & shale	2255
lime brkn & shale	2490
lime	2815
shale & lime	2880
lime	2915
shale & lime	2930
lime	3230
shale & lime	3233
conglomerate	3251
Arbuckle	3255
lime	3266
Total Depth	

Tops:

Anhydrite	315
Brown Lansing	2878
Lansing	2902
Conglomerate	3239
Simpson	3248
Arbuckle	3249

500 A - 2 1/2 BFPH (30 BO)
20 qts Nitro G.
Swb. 5 BWPH - SSO
test 30 to 35 BOPD plus
25 to 30 BWPD