


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - BAY PETROLEUM CORP.
Farm - DeWitt "A" No. 5.

SEC. 9 T. 20 R. 9 W
SE NE SE

Total Depth. 3260
Comm. 12-1-45 Comp. 2-23-46
Shot or Treated.
Contractor. Gabbert Drlg. Co.
Issued. 3-23-46

County. Rice
KANSAS



CASING:
8 5/8" 211'
5 1/2" 3242'

Elevation. _____

Production. Pot. 27 BO, 30 BW
Pmpg.

Figures Indicate Bottom of Formations.

clay sand shale	0-155
shale & shells	211
red bed	307
anhydrite	325
red bed shale & shells	560
shale & shells	915
salt	1095
shale & shells	1200
lime	1290
lime & shale	1800
shale & shells	1995
lime & shale	2110
shale & shells	2275
shale	2385
lime	2395
lime & shale	2495
lime	2840
lime brkn	2889
lime	3100
lime & shale	3175
lime	3205
shale	3237
lime	3245

3245 = 3244 Corr.

dolomite 3244-3260

Total Depth

DP DD 3253 Sfo

Swb 10 GO 30 GWPH

DD 3260

hole caving badly because
of rotten dolomite

Swb 25 GO, 5 GWPH

500 A Swb 3 1/2 BFPH 50% Wtr.

ran liner

ran 29'5" 4" liner.

slotted liner on bottom

dolomite 3244-3260

Geol. Data

Tops:

Anhydrite 307

Brown

Limestone 2881

Lansing

Limestone 2902

Simpson Sh ? 3236

Arbuckle Dolo. 3240