


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk Bldg., Wichita, Kansas

Company - BAY PETRO. CORP.  
Farm Proffitt "B" No. 1

SEC. 9 T. 20 R. 9.W  
SW SE NW

Total Depth. 3244 $\frac{1}{2}$ '  
Comm 9-16-45 Comp. 11-28-45  
Shot or Treated. Acidized  
Contractor.  
Issued. 3-30-46

County. Rice  
KANSAS



CASING:  
8 5/8" 160'  
5" 3230'

Elevation. \_\_\_\_\_

Production. Est. 100 B.

|                      |                    |
|----------------------|--------------------|
| surface clay         | 0-35               |
| shale & sand         | 144                |
| shale                | 160                |
| shale & red bed      | 317                |
| anhydrite            | 337                |
| shale                | 402                |
| shale & shells       | 835                |
| shale & salt         | 1200               |
| lime                 | 1219               |
| shale & shells       | 1497               |
| lime                 | 1502               |
| lime chert           | 1522               |
| lime                 | 1529               |
| lime & chert strks   | 1580               |
| lime & chert         | 1608               |
| lime cherty          | 1615               |
| lime & shale         | 1863               |
| lime                 | 2060               |
| shale & lime         | 2147               |
| shale & shells       | 2234               |
| lime & shale         | 2485               |
| shale                | 2505               |
| lime                 | 2610               |
| cherty lime          | 2637               |
| lime                 | 2746               |
| lime & shale         | 2901               |
| lime                 | 2905               |
| shale & lime         | 3052               |
| lime                 | 3089               |
| lime & shale         | 3110               |
| lime (T.D.w/Rot.)    | 3236               |
| dolomite             | 3244 $\frac{1}{2}$ |
| Total Depth. (cable) |                    |

Figures indicate Bottom of Formations.

Tops:  
Anhydrite 317  
Brown Lansing 2885  
Lansing 2905  
Arbuckle 3233

Porosity 3230-34' odor & stain

Testing Record:  
DD to 3238' show free oil  
500 Acid did not take  
500 Acid Swb 12-15-BOPH