


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - BAY PETROLEUM CORP.
Farm - Proffitt "B" No. 2.

SEC. 9 T. 20 R. 9 W
CWL NE NW

Total Depth. 3247
Comm. 11-11-45 Comp. 12-26-45
Shot or Treated.
Contractor.
Issued. 3-30-46

County. Rice
KANSAS



CASING:
8 5/8" 176'
5 1/2" 3224'

Elevation. _____

Production. Est. 50 B

Figures Indicate Bottom of Formations.

sand & shale	0-171
sand, shale, red	
bed	310
anhydrite	340
shale & shells	849
salt	985
shells & shale	1165
anhydrite	1215
shale & shells	1495
cherty lime	1512
lime	1535
shale & lime	1605
lime cherty	1683
lime & shale	1965
shale	2014
shale & lime	2187
lime	2216
shale & lime	2371
lime	2433
shale	2479
lime & shale	2610
cherty lime	2630
lime	2785
shale & lime	2940
lime	2976
lime & shale	3019
lime	3044
shale & lime	3132
lime (Rotary T.D.)	3225
dolomite	3247
Total Depth	

Tops:

Anhydrite	310
Lansing	2908
Conglomerate	3218
Arbuckle	3223

RTD 3226 SSO
CTD 3247

Testing Record:

1/2 BOPH Natural @ 3243
500 Acid-Swab 1 1/2 BOPH
Reacidized - 3238-45
with pitot - 500 gals.
Swb 2 1/2 BOPH
Est. 50 BOPD