


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

CITIES SERVICE OIL CO.
Dick No. 1.

SEC.9 T.20 R.9 W
CEL NE SW
660'S 330'W of Center

Total Depth. 3256'
Comm. 4-5-42 Comp. 4-21-42
Shot or Treated.
Contractor. Corbett-Barbour Drlg.Co.
Issued. 6-6-42

County. Rice



CASING:
8 5/8" 255' Cem.
5 1/2" 3243' Cem.

Elevation.

Production. Temp.Phy.Pot.
79 BO, no wtr
Figures Indicate Bottom of Formations

surface sand	0-225
shale & shells	255
red bed, shale, shells	405
shale & shells	830
shale, salt, shells	1150
anhydrite	1206
brkn lime & shale	1260
shale & shells	1370
lime brkn	1425
shale & shells	1520
lime brkn	1745
lime & shale	1895
lime brkn & shale	2000
lime brkn	2056
shale & shells	2205
lime brkn	2330
shale	2373
lime brkn	2550
lime	2615
lime & strks shale	2675
lime brkn sft	2713
lime hrd	2768
lime	2800
shale & shells	2922
shale	2962
shale & lime	2994
lime	3245
3245 Rot.TD=3243 SLM	
lime	3256
Total Depth.	

500 Gals. 4-24-42
740 Gals. 4-25-42
1286 Gals. 4-27-42
1500 Gals. 5-1-42

Corr. Top Eros. Arbuckle 3229
Corr. Top Arbuckle 3238
Penetration 18

Fillup: 260' oil in 2 hrs
450' oil in 3 hrs
500' oil in 4 hrs
775' oil in 16 hrs
4-29-42 shot w/10 Qts.
S.N., 3246-50; 100' sand
tamp.