

WELL LOG BUREAU * KANSAS GEOLOGICAL SOCIETY.
 Union National Bank Bldg, Wichita, Kansas

GYPSY OIL COMPANY.
 E.M. Dewitt No. 2

SEC. 9 T. 20 R. 9W.
 NEc SE


CORRECTED LOG

Total Depth. 3288
 Comm. 7-6-35 Comp. 7-24-35
 Shot or Treated.
 Contractor.
 Issued. 10-26-35

County. Rice.

CASING.

12 1/2" 209'
 6 5/8" 3238'
 7" 3241'



Elevation.

Production. Pot. 560 B.

Figures Indicate Bottom of Formations

no log 209
 shale 2380
 lime 3185
SAMPLE LOG
 lime 3213
 Var. col. shale & lime 3228
 Var. col. shale, sand,
 and milky chert 3239
 dolomite 3288
 Total Depth.
 Top of Siliceous lime 3239
 Plugged back to 3271

Plug back 3288 to 3282 with lead wool
 and then plug back 3282 to 3271 with
 crushed rock.

7-27-35 Shot 40 qts 3255-3271. After
 cleaning out had 2500' oil in hole.

7-28-35. Swabbed 320 bbls oil in 19 hrs.
 Averaged 14 B.O. PH during last 8 hours.
 swabbing from bottom.

7-31-34 Acidized 1000 gal.

8-4-35. 24 hour State potential test.
 made 560 bbls oil and 2 BW.

Standardized at 3243.

NOTE- The following two steel
 line corrections have been applied
 to the above sample log.
 3239 equals 3241
 3241 equals 3243

HISTORY

Cored 3241 to 3271 a few slight
 oil stains. At 3271 made 1 B.O. in
 2 hours. Stood 6 hours and made 4 1/2
 bailers oil.

Cored 3271-3286 - no increase in
 oil. Show water 3286-3288