

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company C. U. BAY
Farm Keesling "A" No. 2.

SEC. 10 T. 20 R. 9 W
SE NW SW

Total Depth. 3234
Comm. 11-18-45 Comp. 12-3-45
Shot or Treated.
Contractor. Mercury Dlg Co.
Issued. 3-30-46

County. Rice
KANSAS



CASING:
8 5/8" 183' Cem.
5 1/2" 3221' Cem.

Elevation. _____

Production. Est. 50 BOPD
show wtr.

Figures Indicate Bottom of Formations.

surface sand & clay	0-50
sand	140
shale	185
red bed & shale	295
anhydrite	315
red bed & shale	490
red bed	700
shale & shells	960
salt	1150
shale & shells	1170
shale & lime	1370
lime	1650
shale	1710
shale & lime	2050
shale & shells	2190
shale & lime	2285
lime	2330
lime & shale	2420
lime sdy	2450
lime	2804
lime & shale	2870
shale	2905
lime	3025
lime & shale	3210
lime	3234
Total Depth	

Tops:
Anhydrite 295
Lansing 2905
Conglomerate 3217
Arbuckle 3219

Rotary T.D. 3222
Cable T.D. 3234

DP DD 3233
2/3 BOPH
DD 3234
500 A
Swb 2 BO 5 G/PH
POP