


SHARON DRILLING CO., INC.
 Tappan No. 1.

SEC. 10 T. 20 R. 9W
 CWL NW NE

Total Depth. 3240'
 Comm. 9-27-40 Comp. 10-18-40
 Shot or Treated. No acid
 Contractor.
 Issued. 11-9-40

County. Rice



CASING:
 8 5/8" 203'
 5" 3223'

Elevation.

Production. Pot. 415 B. Pump Nat.

Figures Indicate Bottom of Formations.

clay	30
sand	45
shale	70
sand	120
shale sand	180
shale shells	205
sand, shale, shells	268
anhydrite	290
shale sand	330
shale, shells, red rock	560
lime brkn, shale	800
shale, salt	1015
shale & shells	1160
shale & lime	1275
brkn lime	1350
brkn lime sand	1460
lime	1535
shale & lime	1595
lime	1650
shale	1675
lime	1735
shale & lime	1860
lime	1890
shale	2005
shale & shells	2145
shale	2175
lime	2205
shale & shells	2230
lime	2270
shale & shells	2340
lime	2360
shale & shells	2435
lime	2770
shale & shells	2895
lime	3165
shale & lime	3198
shale red	3215
shale green Simps on	3218
chert Arbuckle	3222
dolomite	3240
Total Depth.	

Initial potential 415 B. Pump
 Nat.

Cored 3198-3215 red shale &
 ls ledge

Cored 3231-3240 Arbuckle dol.

Geological Tops:

Anhydrite	268
Ft. Riley	1355
Topeka	2440
Dodge	2846
Lansing	2872
Marmaton red shale	3186
Simpson shale	3215
Arbuckle chert	3218
Arbuckle dolomite	3222