


STANOLIND OIL & GAS CO.
Oscar L. Smith No. 1.

SEC. 16 T. 20 R. 9W.
NEc SE
2310' N of SL 2310' E of W.L.

Total Depth. 3261.
Comm. 10-22-35 Comp. 11-13-35.
Shot or Treated.
Contractor.
Issued. 12-28-35. Rotary 0 to 3238
Cable 3238 to 3261

County. Rice.



CASING.

13" 187' 7" 3229'

Elevation.

Production. 1502 bbls.

Figures Indicate Bottom of Formations.

surface clay	35
sand and shale	155
shale and lime shells	187
red rock and shale	625
shale and shells	830
salt	1070
shale and shells	1290
lime	1385
shale	1425
shale and lime	1550
broken lime	1635
shale and shells	2360
shale	2440
lime	2655
broken lime and shale	2750
broken lime	2880
shale	2885
shale and lime	2930
lime	3205
shale	3224

CORING RECORD.

limo red & Gr shale 3225
lime with gr and red
shale partings some chert 3228
lime Gr and red shale and
chert 3232
lime red, shale and Gr.
shale 3233
dolomite show oil 3238
dolomite(cable tool) 3261 show oil
Total Depth.
Swabbed 60 bbls an hour from 2700 feet at 3261.

siliceous 3233-3261.