

29-21-1W  
Plotted Texas CO.


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY:  
Union National Bk Bldg, Wichita, Kansas.

CONTINENTAL OIL CO:  
A.K. Graber # 2

SEC 29 T. 21 R. 1W.  
CEL W $\frac{1}{2}$  SE  
1320' N 990' E of S/4 cor.

Total Depth. 3314.  
Comm. 4-9-36 Comp. 5-5-36.  
Shot or Treated.  
Contractor.  
Issued. 6-13-36.

County, McPherson JUN 13 1936



CASING:

16" 148' 7" 3299'

Elevation.

Production. Pot. 813 B.  
24 Hr.

Figures Indicate Bottom of Formations.

sand	20	5-6-36	2350' oil
shale and shells	80	5-7-36	Swab 125 bbls 2 hours.
lime	110	5-10-36	2000 gal acid.
shale and lime	148	5-12-36	703 bbls 19 hrs on Pot.
lime	150	5-13-36	813 bbls 24 hrs on Pot.
shale	218		
shale and shells	340		
lime	368		
broken lime	478		
shale	488		
red bed	503		
broken lime	578		
shale and shells	678		
lime	694		
shale and shells	1028		
shale	1490		
shale and shells	1610		
shale	1720		
lime	1780		
broken lime	2097		
shale and shells	2300		
broken lime	2320		
lime	2694		
broken lime	2731		
shale	2756		
broken lime	2870		
shale	2913		
shale and shells	2928		
chat	3071		
lime	3168		
lime	3233		
shale	3300		
Hunton lime	3314	Total Depth.	

GEOLOGICAL TOPS:

Top Kansas City 2310'  
Top chat 2928  
Top Hunton 3300' corr.

Correction 3294 equals 3300'