


CONTINENTAL OIL CO.  
 J.C. Goering No. 2.

SEC. 29 T. 21 R. 1W  
 NE c SW  
 330' S & 330' W NE  
 c SW $\frac{1}{4}$   
 County. McPherson

Total Depth. 3308'  
 Comm. 5-1-36. Comp. 5-27-36.  
 Shot or Treated. 2000 Gals. Acid.  
 Contractor.  
 Issued. 7-11-36

Casing:

13" 137'  
 7" 3271'



Elevation.

Figures Indicate Bottom of Formations. Production. Pot. 517 B. Oil.

surface clay	15
shale & shells	126
shale	136
lime	138
shale	283
shale & shells	535
broken lime	565
shale & shells	677
broken lime	849
shale	987
shale & shells	1120
shale	1291
shale & shells	1666
shale	1680
lime	1306
broken lime	1836
shale & shells	1896
lime	1918
broken lime	2090
shale & shells	2171
broken lime	2285
shale	2295
lime	2684
broken lime	2818
shale & shells	2883
shale	2915
chat	3040
lime	3200
shale	3270
Hunton lime	3303
shale & lime	3308
Total Depth	

800' oil in hole 3296  
 1700' oil in hole 3308

6-1-36 acidized with 2000 gallons acid.  
 6-2-36, pumped 469 bbls. in 17 hours.  
 6-3-36, pumped 517 bbls. 24 hr. Potential test.

Geological Tops: Top Kansas City lime 2295'  
 Top chat 2915'  
 Top Hunton lime 3270'