

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bk Bldg., Wichita, Kansas.


CONTINENTAL OIL CO.  
J. C. Goering No. 6.

SEC. 29 T. 21 R. 1W  
SWc SW  
330' N & 330' E SWc

Total Depth. 3279'  
Comm. 10-27-37 Comp. 11-20-37  
Shot or Treated.  
Contractor.  
Issued. 1-8-37 Rotary O-3258  
Cable 3258-79

County. McPherson

CASING:  
10" 160'  
7" 3258'



Elevation.

Production. Pot. 542 B.

Figures Indicate Bottom of Formations.

shale & shells	65	
lime	70	
sand	85	Hunton line 3257-3278
shale & shells	138	
lime	139	
shale	159	
lime	160	
shale & shells	683	
brkn lime	788	
shale & shells	814	
lime	831	
brkn lime	853	
shale & shells	1703	
brkn lime	1789	
lime	1930	
brkn lime	2291	
lime	2678	
shale & shells	2740	
brkn lime	2798	
shale & shells	2900	
chat	3058	
lime	3170	
brkn lime	3220	
shale	3257	
Hunton lime	3278	
shale	3279	
Total Depth.		

Hole filled up 1000' with oil 3258-3260

Hole filled up 1500' with oil 3264-3278