


CONTINENTAL OIL CO.  
F.A.Hetzke No. 8.

SEC. 29 T. 21 R. 1W  
CEL W $\frac{1}{2}$  NE  
1320'S 990'E of N/4 Cor.

Total Depth. 3326'  
Comm. 7-13-37 Comp. 8-10-37  
Shot or Treated. 4000 Gals. Acid.  
Contractor.  
Issued. 10-2-37

County. McPherson



CASING:  
10" 145'  
7" 3284'

Elevation.

Production, Pot. 752 B.

Figures Indicate Bottom of Formations.

shale	15
sand	25
shale & shells	45
sand	60
shale	85
shale & shells	140
shale	144
lime	148
shale & shells	849
shale	900
shale & shells	1737
brkn lime	1775
brkn lime & shale	1856
brkn lime	1875
lime	1956
lime & shale	2098
lime	2110
shale & shells	2135
brkn lime	2263
shale & shells	2286
lime	2666
shale	2906
chat	3055
lime	3163
shale	3283
Hunton lime	3326
Total Depth.	

500' oil in hole 3286-3291  
1500' oil in hole 3291-3296  
2000' oil in hole 3296-3301