

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.


CONTINENTAL OIL CO.
F. A. Hetzke No. 11

SEC. 29 T. 21 R. 1W.
SW SE NE
330' N 990' W of E $\frac{1}{4}$ cor

Total Depth. 3338
Comm. 2-11-38 Comp. 3-8-38
Shot or Treated.
Contractor.
Issued. 5-21-38

County McPherson.

CASING. Rotary 3299
Cable 3338



10" 147'
7" 3299'

Elevation.

Production Pot. 481 B.

Figures Indicate Bottom of Formations.

surface clay	10	
sand	20	
shale and shells	145	
lime	147	
shale and shells	509	
broken lime	875	
shale and shells	1715	
lime	1735	
broken lime	1924	
lime	1995	
broken lime	2070	
lime	2140	
sdv shale	2220	
broken lime	2297	
lime	2741	
shale and shells	2925	
chert	2938	
chat	3045	
lime	3200	
dolomite	3210	
shale and shells	3247	
shale	3298	
Hunton lime	3338	show of oil 3308-3315

Total Depth.

Hunton lime 3298-3338