

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.

CONTINENTAL OIL CO.
J.P. Huxman No. 2.

SEC. 29 T. 21 R. 1W
NEc NW
330' S 330' W of NEc NW $\frac{1}{4}$

Total Depth. 3323'
Comm. 5-4-37 Comp. 6-5-37
Shot or Treated.
Contractor.
Issued. 7-17-37

County. McPherson

Rotary O-3275
Cable 3275-3323



CASING:
10 3/4"
7

129'3"
3298'2"

Elevation.

Production. Pot. 644 B.

Figures Indicate Bottom of Formations.

sand & surface clay	20
shale	56
shale & shells	126
shale & lime shells	135
lime	137
shale & shells	302
brkn lime	442
shale & lime shells	567
brkn lime	647
shale & shells	752
shale & lime	837
shale & lime shells	1400
brkn lime	1457
shale	1572
shale & shells	1747
brkn lime	2130
shale & shells	2166
brkn lime	2298
lime	2670
shale & shells	2781
lime	2811
shale & shells	2896
shale	2898
chat	3029
lime	3180
dolomite	3200
shale	3274
Hunton lime	3322
shale & lime blue	3323
Total Depth.	

Showing of oil at 3278 to 3283
Increase in oil from 3283 to 3288
Increase in oil and gas from 3293 to 3299
Hole filled up 800' with oil from 3299 to 3304
1500' oil in hole from 3304 to 3318

Hunton Line 3274-3322