

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


16-21-1W

Company - BRANINE & HOLL
Farm - Lena Meushke No. 1.

SEC. 16 T. 21 R. 1 W
SW NW NE

Total Depth. 3469'
Comm. 2-12-44 Comp. 2-28-44
Shot or Treated.
Contractor.
Issued. 5-13-44

County. McPherson
KANSAS



CASING:
8 5/8" 243'

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

surface soil & sand 0-15
shale 100
shale & shells 500
lime sdy 615
lime & sand 800
shale & shells 2055
lime 2100
shale 2220
sand 2257
shale 2325
lime 2470
lime & sand 2550
lime 2600
lime & shale 2690
lime 2815
shale & lime 2940
lime & chert 3020
lime brkn 3115
chert 3135
lime & chert 3160
chert 3195
chert, shale, lime 3220
chert 3230
shale 3235
shale, strks lime 3285
shale 3377
lime 3392
shale 3452
lime 3469
Total Depth.

Tops:
Lansing 2320
Miss. 2334
Kinderhook Shale 3237 (Base Miss.)
No Hunton
No Misener
Maquoketa (Sylvan Shale) 3343 (Base Kind.)
Viola 3452 (Base Maquo. Shale)
Total Depth 3469 no shows
no shows worth testing

21 21 1 W
16 21 1 W