

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.

20-214W
Leo Norcross

Plotted Texas CO.


CONTINENTAL OIL CO.
F.A.Hetzke "A" No. 1.

SEC. 20 T.21 R.1W
SE SW SE
330' fr SL 990' fr WL SE $\frac{1}{4}$

Total Depth, 3310'
Comm. 6-1-36 Comp. 7-6-36
Shot or Treated, 4000 Gals. Acid.
Contractor, L.W.Prunty Drlg.Co.
Issued, 9-12-36

County, McPherson

SEP 12 1936



CASING:

13" 142'
7" 3299'8"

Elevation.

Production, 1634 B.

Figures Indicate Bottom of Formations.

surface clay	10
sand	50
lime	90
sand hrd	100
lime	105
shale	107
shale & shells	137
lime	150
shale	275
lime	324
brkn lime	424
shale & lime shells	496
lime	516
shale	536
brkn lime	545
lime	561
brkn lime	640
lime	680
shale & shells	698
lime	748
brkn lime	789
lime	870
brkn lime	950
shale & shells	1503
shale & lime shells	1580
lime	1603
shale & shells	1741
lime	1811
shale	1816
lime	1826
shale	1851
lime	1876
brkn lime	1886
lime	1919
lime hrd	1961
lime	2007
shale	2019
brkn lime	2025
lime	2028
shale & shells	2039

brkn lime	2836
brkn lime & shale	2882
lime	2908
chat	3041
Show of oil 2925 to 2940	
3/4 Million gas, No oil at 2950	
Bottom hole pressure open flow 75#	
Closed 4 minutes and rocked up	
to 1000#.	
lime	3180
sd lime	3195
lime	3221
shale sticky	3231
shale	3278
Top Hunton 3280'	
lime Hunton	3310'
Total Depth.	

Geological Tops:

Top Chat	2892' Corrected.
Top Hunton	3285' Corrected.

lime	2041
brkn lime	2100
shale & shells	2160
shale	2190
lime	2272
brkn lime	2280
shale	2290
lime	2763
brkn lime & shale	2810