

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg, Wichita, Kansas.

28-25-190
Albert Wheeler

CONTINENTAL OIL CO.
A.E. Kindblade No. 3


SEC. 20 T. 21 R. 1W.
Sec SW
330' N 330' W. S $\frac{1}{4}$ cor.

Total Depth. 3326
Comm. 8-25-37 Comp. 6-22-37
Shot or Treated.
Contractor.
Issued. 8-21-37

Rotary 3279
Cable 3326

AUG 21 1937

County McPherson.



Elevation.

CASING.

10" 137' 7" 3300'

Production. Pot. 682 B.

Figures Indicate Bottom of Formations.

shale	12
sand	23
shale and sholls	143
lime	146
shale and shells	696
broken lime	753
sand	767
lime	782
shale	890
lime	920
shale	957
shale and shells	1270
shale	1465
shale and shells	1595
lime	1615
shale and shells	1675
shale	1740
lime	1820
shale and shells	1928
broken lime	2126
shale	2239
shale and lime sholls	2290
shale	2296
lime	2649
broken lime	2721
shale and shells	2897
chat	3055
lime	3181
broken lime	3205
shale	3277
lime Hunton	3326
Total Depth.	

show of oil 3286-3291
more oil 3291-3296
hole filled up 1000 ft with oil
in one hour from 3301 to 3306
Hole filled up 1800 ft with oil
from 3314 to 3326

Hunton lime 3277-3326