


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- LARIO OIL & GAS CO.
Farm- Brandt No. 1

SEC. 1 T. 21 R. 1W
SW SW SE

Total Depth. 3400'
Comm. 5-16-58 Comp. 5-27-58
Shot or Treated.
Contractor.
Issued. 8-9-58

County McPherson
KANSAS



Elevation. 1539' RB

CASING:
8 5/8" 215' cem w/180 sx.
5 1/2" 3412' cem w/75 sx.

Production. 33 BO & 11 BW
24 hrs. physical

Figures Indicate Bottom of Formations.

clay	35
sand	70
shale	310
shale & shells	400
shale & lime streaks	555
shale & lime	775
lime	930
shale & lime	1300
shale & lime stks	1620
lime & shale	1795
shale & lime	1945
lime & shale	2060
shale & lime	2210
sand & shale	2270
shale & lime	2365
lime	2550
lime & shale streaks	2650
lime	2884
lime & shale	2973
Mississippi lime	3003
lime	3088
lime & chert	3128
cherty lime	3188
lime	3262
shale & lime	3290
shale	3394
shale & lime	3396
Hunton lime	3400 RTD
Total Depth	

TOPS: RB MEAS.

Brown Lime	2333
Lansing	2342
Mississippian	2961
Kinderhook	3261
Hunton	3396