

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ANDERSON-PRICHARD OIL CORP.
Farm- Klassen Unit No. 2

SEC. 12 T. 21 R. 1W
NE NW SE

Total Depth. 3408'
Comm. 1-9-59 Comp. 1-18-59
Shot or Treated.
Contractor. Peel Brothers, Inc.
Issued. 3-21-59

County McPherson
KANSAS



Elevation. 1536' RB

Production. 22 BO & 34 BWPD

CASING:

8 5/8" 225' cem.
4 1/2" 3402' cem.

Figures Indicate Bottom of Formations.

clay & sand	85
shale	350
lime & shale	930
shale	1440
shale & lime	2260
shale	2370
lime & shale	2850
lime	2930
shale & lime	3010
chert & lime	3225
lime & shale	3404 RTD
lime & shale	3408 CTTD
Total Depth	

TOPS: CORR.	
Mississippi	2981
Kinderhook	3272
Hunton	3402

Drilled cement & CO to RTD 3404. DD
3404-06 Good show oil. DD 3406-08,
increase in show. After 11 hrs, FU 40'
oil & 5' formation water.
Az w/500 gal. Rec. load. Swbd 4 BFPH,
20% oil. POP.