

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

UNION NATIONAL BANK BLDG WICHITA KANSAS.

Location SE cor SW NE.

Sec. 7 T. 21 R. 10W

Casing Record

County- Rice.

10" 2152 Farm- Miller No. 1
 20" 107 8 1/2" 2856 Company- Boucher Oil Company.
 15 1/2" 637 65/8" 3409'8" Contr.- R. P. Mays.
 12 3/4" 1519 53/16" Comm.- 8/2/30 Comp.- 12/12/30.
 Total Depth 3417'. Shot Quarts Between
 Correspondence Regarding This Well Should Be Referred to



Figures Indicate Bottom of Formations.

Elevation Initial Production Dry.

Date Issued. 1/10/1931.

Formation	Depth	Formation	Depth
sand	107	red rock	2225
red rock 7 BW	280	shale blue	2270
sand	290	lime	2295
red rock	430	shale blue	2335
lime 6 BW	450	lime	2355
red rock	630	shale blue	2405
shale blue	645	lime	2425
red rock	730	shale blue	2440
slate blue	790	lime	2445
red rock	825	shale blue	2490
slate blue	945	lime	2495
salt	1265	shale blue	2500
shale blue	1275	lime	2510
lime	1285	shale blue	2520
shale blue	1305	lime	2545
lime	1310	shale blue	2560
brkn lime	1380	sdv lime HFW	2575
red rock	1390	slate blue	2595
lime	1405	lime white	2665
slate blue	1480	lime sft HFW	2672
sdv shale show gas	1495	lime white	2765
red rock	1519	shale blue	2770
lime 5 BW	1630	lime	2775
sdv lime	1650	shale blue	2800
red rock	1665	sdv lime	2825
lime	1675	shale blue	2830
shale blue	1710	lime	2880
lime	1730	shale blue	2920
shale blue	1750	red rock	2930
red rock	1760	shale blue	3015
lime	1770	lime	3020
shale blue.	1800	shale	3045
red rock	1825	lime 10 BW 3165	3250
shale blue	1840	brkn lime	3260
sdv shale 4 BW	1850	lime	3315
sdv lime	1880	various colored shale	3330
HFW 1875'		lime sdv water	3350
shale blue	1895	conglomerate	3355
red rock	1908	sand HFW	3392
lime	1916	conglomerate	3397
shale blue	2000	shale green	3410
lime gray HFW	2010	Silicious lime	3417
shale blue	2020	HF sulphur water 3415-	3417
lime	2030		
shale blue	2115	Total Depth	3417
lime	2120		
shale blue	2145		
lime	2160		
shale blue	2220		