


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

ALPINE OIL & ROYALTY CO.
Gish No. 1

Sec. 16 T. 21 R. 10 W.
CE $\frac{1}{2}$ NE SE

Total Depth. 3474
Comm. 8-3-42 Comp. 8-18-42
Shot or Treated.
Contractor. Sharon Drilling Co.
Issued. 8-29-42

County Rice.



CASING.

8" 162' cemented.

Elevation.

Productions. DRY

Figures Indicate Bottom of Formations

surface	8
sand	120
sdv red shale	162
red bed	170
red bed and shale	370
anhydrite	405
shale and shells	900
salt	1105
shale and shells	1250
broken lime	1605
sand	1620
broken lime	1650
shale and shells	1700
broken limo	1815
shale and shells	2253
limo	2266
shale and shells	2318
broken limo	2455
shale and shells	2473
broken limo	2528
sdv shalo	2556
sand	2576
lime Topoka	2775
broken lime	2835
lime	2888
shalo and shells	3051
lime	3303
shale and limo	3339
chert&congl.	3379
shaly sand	3383
cored 3381 to 3390 Full Recovery.	
3' of tight shaly sand and	
6' of green shalo.	
shale groon	3424
Arbucklo dolomito	3474
Total Depth.	

Ran Schlumberger - no shows.

TOPS - sand	2556
Topoka lime	2576
Lansing	3015
Chert Congl.	3339
Simpson	3379
Arbucklo	3424