


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- STRATA DRILLING, INC.
 Farm- Gish No. 1

SEC. 16 T. 21 R. 10W
 NW NE NE

Total Depth. 3406'
 Comm. 10-24-59 Comp. 10-31-59
 Shot or Treated.
 Contractor. Strata Drlg.
 Issued. 1-30-60

County Rice
 KANSAS



Elevation. 1720' RB

Production. 44 BOPD

CASING:

8 5/8" 195' cem w/175 sx.
 5 1/2" 3403' cem w/75 sx.

Figures Indicate Bottom of Formations.

sand & clay	75
shale	1190
shale, lime strks	1375
shale & lime	3341
limestone, shale & sand	3375
lime	3406
Total Depth	

TOPS: SCOUT

Heebner	2843
Brown Lime	2976
Lansing	3002
Conglomerate	3305
Simpson	3330
Arbuckle	3400

DST #1 3307-3375', op 1 hr., rec. 2430'
 water, IFP 270#, FFP 1070#, BHP 1130#/20 mins.

DST #2 3400-3406', op 1 hr, strong blow,
 rec. 2700' oil, 460' water. IFP 450#,
 FFP 1110#, BHP 1130#/20 mins.