

F. G. HOLL COMPANY
KEELER 'C' 1-20
260'W & 30'N of N/2 NW NW
Sec 20-21S-11W
Stafford Co. Ks.

API #15-185-22924

KCC

DST INFORMATION

NOV 23

CONFIDENTIAL

- DST 1: Lansing, 3226-3252, 15-30-15-30
1st Blow: Weak blow, died in 12 min.
2nd Blow: No blow
IHP 1594 FHP 1583 IFP 65-55 ISIP 568 FFP 66-55 FSIP 390 BHT 108°
Rec: 15' mud w/slt show of oil on top of the tool.
- DST 2: Lansing, 3310-3385, 30-60-60-90,
1st Blow: Weak blow
2nd Blow: Weak blow
IHP 1715 FHP 1660 IFP 78-66 ISIP 256 FFP 78-66 FSIP 234 BHT 109°
Rec: 40' slt oil cut mud (5% oil, 95% mud), 60' GIP
- DST 3: Viola Chert, 3390-3465, 15-30-15-30
1st Blow: Weak blow, died in 12 min.
2nd Blow: No blow
IHP 1738 FHP 1726 IFP 100-89 ISIP 656 FFP 100-89 FSIP 612 BHT 111°
Rec: 10' mud w/few spots of oil.
- DST 4: Simpson Sand, 3460-3488, 30-60-30-60
1st Blow: Weak blow
2nd Blow: Weak blow, died in 4 min.
IHP 1815 FHP 1771 IFP 55-66 ISIP 678 FFP 66-66 FSIP 678 BHT 111°
Rec: 10' slt oil cut mud (95% mud, 5% water), 60' slt oil cut mud (85% mud, 15% water), good show of oil on top of the tool.

RELEASED

JAN 11 1996

FROM CONFIDENTIAL