

F. G. HOLL COMPANY

6427 EAST KELLOGG - P.O. BOX 780167
WICHITA, KS 67278-0167

COPY

CONFIDENTIAL

AP2#15-185-22712
ACO-1 (Continued)RE: RADER #4-18
NE NW SE, Sec 18-21s-11w
Stafford County, KSDST #1 (3350-3380) LKC "J" ZONE

1) WB Dead in 2.5 mins. 2) NB, Flush, NB

REC: 70' DM

IHP: 1685	IFP: 65-44:30"	ISIP: 43:30"	BHT: NA
FHP: 1651	FFP: 42-88:30"	FSIP: 179:30"	CHL: NA

DST #2 (3424-3466) CONGLOMERATE

1) WB Dead in 2", Flush, NB 2) NB

REC: 5' DMw/Show Oil on Tool

IHP: 1718	IFP: 69-50:30"	ISIP: 50:30"	BHT: 106F
FHP: 1698	FFP: 49-49:30"	FSIP: 49:30"	CHL: NA

DST #3 (3466-3515) SIMPSON SAND

1) NB, Flush, WB Dead in 13 mins. 2) NB

REC: 10' DM

IHP: 1743	IFP: 74-57:30"	ISIP: 63:30"	BHT: 106F
FHP: 1759	FFP: 60-60:30"	FSIP: 63:30"	CHL: NA

DST #4 (3535-3540) ARBUCKLE

1) Weak Intermittent Blow Dead in 13 mins. 2) NB, Flush, Weak Steady 1/4" Blow

REC: 55' OCM (12%O, 88%M)

IHP: 1758	IFP: 12-19:30"	ISIP: 1131:45"	BHT: 106F
FHP: 1694	FFP: 47-30:30"	FSIP: 1049:45"	CHL: NA

DST #5 (3540-3545) ARBUCKLE

1) NB, Flush, NB 2) NB, Flush, NB

REC: 5' DM

IHP: NA	IFP: NA :15"	ISIP: NA :15"	BHT: NA
FHP: NA	FFP: NA :15"	FSIP: NA :15"	CHL: NA

CHARTS SHOW PLUGGING ACTION.

DST #6 (3540-3550) ARBUCKLE

1) No Packer Seat, Reset, WB Dead in 1" 2) NB, Flush, WB Dead

REC: 220' SltoSpkMud

60' SltoCM (6%O, 94%M)

60' SltoGCM (14%G, 14%O, 72%M)

60' SltoGCM (20%G, 15%O, 65%M)

400' Total Fluid

IHP: 1777	IFP: 210-211:30"	ISIP: 1119:30"	BHT: 108F
FHP: 1712	FFP: 204-213:30"	FSIP: 1083:45"	CHL: NA

RECEIVED
STATE OF KANSAS
WICHITA, KANSAS
JAN 2 1991

RELEASED

JAN 2 4 1993