

Computer Inventoried

F. G. HOLL COMPANY

6427 EAST KELLOGG - P.O. BOX 780167
WICHITA, KS 67278-0167

RELEASED

MAR 05 1992

ORIGINAL
CONFIDENTIAL

AP2# 15-85-22615

FROM CONFIDENTIAL

KLEIN 1-18

DST #1: 3178-3240 LANSING

30-30-30-30

IFP 68/33:30 ISIP 44:30 FFP 36/33:30 FSIP 41:30

IHP 1590 FHP 1578 BHT 102°

Recovered 20 feet of mud.

DST #2: 3332-3395 KANSAS CITY

30-60-60-90

IFP 68/55:30 ISIP 592:60 FFP 107/77:60 FSIP 600:90

IHP 1714 FHP 1653 BHT 110°

Recovered 5 feet of very slightly oil cut mud and 60 feet of mud with a few specks of oil.

DST #3: 3490-3500 ARBUCKLE

30-60-60-90

IFP 34/115:30 ISIP 1081:60 FFP 187/220:60 FSIP 1019:90

IHP 1715 FHP 1707 BHT 112°

1st Opening: Weak blow-built to bottom of bucket in 13 minutes.

2nd Opening: Weak blow-built to bottom of bucket in 23 minutes.

Recovered 570 feet of clean gassy oil (37% gas, 62% oil, 1% mud)

Recovered 60 feet of mud cut gassy oil (30% gas, 40% oil, 30% mud)