

TIGHT HOLE

KEELER #1-8  
80'S of W2 SW SW  
Sec 8-21s-11w  
Stafford County, KS  
API#: 15-185-22,696

DST #2 (3379-3426) Arbuckle

- 1) SBOB in 1 min.
- 2) SBOB in 1 min.

REC: 1600' GIP  
1210' SMCGO  
1210' Total Fluid

IHP: 1693 IFP: 232-257:30" ISIP: 822:60"  
FHP: 1691 FFP: 346-403:60" FSIP: 794:90"  
BHT: 108F

DST #3 (3426-3441) Arbuckle

- 1) SBOB in 1 min.

2) SBOB, GTS in 19" Gauge: 2.11 MCFPD in 20"  
1.98 " 30"  
1.59 " 40"

1.29 MCFPD in 50"  
1.29 MCFPD in 60"

REC: 2450 CGO

IHP: 1726 IFP: 489-640:30" ISIP: 878:60"  
FHP: 1679 FFP: 754-828:60" FSIP: 955:90"  
BHT: 108F

RECEIVED  
STATE CORPORATION COMMISSION  
STATE CORPORATION COMMISSION

DST #4 (3441-3456) Arbuckle

- 1) SBOB

2) SBOB, GTS in 30" Gauge: 1.59 MCFPD in 40"  
1.29 MCFPD in 50"  
1.29 MCFPD in 60"

OCT 29 1998

CONSERVATION DIVISION  
Wichita, Kansas

REC: 1140' GO (52%G, 48%O)  
1000' GO (19%G, 81%O)  
180' MW (15%M, 85%W)  
2320' Total Fluid

IHP: 1782 IFP: 575-632:30" ISIP: 884:60"  
FHP: 1637 FFP: 781-838:60" FSIP: 946:90"  
BHT: 109F