

Computer Inventories

F. G. HOLL COMPANY
6427 EAST KELLOGG - P.O. BOX 780167
WICHITA, KS 67278-0167

KEELER "A" #1-8
C NW SW NW
Sec 8-21s-11w
Stafford County, KS
API#: 15-185-22,861

CONFIDENTIAL: "TIGHT HOLE"

RELEASED

DEC 2 2 1994

FROM CONFIDENTIAL

***DST #1 (3296-3338) LKC "I" - "J"

1) WB Died in 10"
2) NB
TIMES: 30"30"30"30"
REC: 10' Mud w/SSO between SI & Hydraulic tools
IHP: 1646# IFP: 48-44#:30" ISIP: 642#:30"
FHP: 1608# FFP: 51-54#:30" FSIP: 444#:30"
BHT: 112F

***DST #2 (3373-3425) BKC - ARBUCKLE

1) WB dec to intermittant blow
2) WB dec to intermittant blow
TIMES: 30"30"30"30"
REC: 20' SO&GCM (23%Gas, 12%Oil, 65%Mud)
50' GIP
IHP: 1703# IFP: 67-46#:30" ISIP: 607#:30"
FHP: 1668# FFP: 60-51#:30" FSIP: 80#:30"
BHT: 113F

NOV 1 6

CONFIDENTIAL

***DST #3 (3425-3435) ARBUCKLE

1) FBOB in 8"
2) FBOB in 8"
TIMES: 30"60"60"90"
REC: 835' GIP
675' CGO
65' O&GCWM (23%G, 12%O, 50%M, 15%W)
740' Total Fluid
IHP: 1686# IFP: 47-129#:30" ISIP: 1089#:60"
FHP: 1682# FFP: 181-252#:60" FSIP: 1093#:90"
BHT: 113F
CHL: 16,000ppm

***DST #4 (3435-3450) ARBUCKLE

1) GBOB in 3"
2) GBOB in 3"
TIMES: 30"60"60"90"
REC: 600' GIP
525' CGO
115' SOCWM (5%G, 5%O, 40%M, 40%W)
120' VSOCWM (3%O, 20%M, 77%W)
120' VSO&MCW (3%O, 10%M, 87%W)
120' VSMCW w/Trace Oil (TraceO, 3%M, 97%W)
1000' Total Fluid
IHP: 1717# IFP: 92-220#:30" ISIP: 966#:60"
FHP: 1663# FFP: 287-399#:60" FSIP: 949#:90"
BHT: 115F
CHL: 16,000ppm

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 0 2 1992

CONSERVATION DIVISION
WICHITA, KS