

Computer Inventories F. G. HOLL COMPANY

6427 EAST KELLOGG - P.O. BOX 780167
WICHITA, KS 67278-0167

AUG 30

CONFIDENTIAL

ACO-1 (Continued)

SMITH "C" 6B-17
SW SW SE, Sec 17-21s-11w
Stafford County, KS

RELEASED

SEP 1 4 1993

FROM CONFIDENTIAL

STATE CORP. RECEIVED
SEP 3 1993
CONSERVATION DIVISION
Wichita, Kansas

DST #1 (3140-3195) LANSING "A" - "D"

1) SBOB in 18 mins. 2) SBOB in 23 mins.

REC: 5' CO

180' SOSptdMud (5%O, 65%M, 30%W)

795' OSptdW (TO, 12%M, 88%W)

975' Total Fluid

IHP: 1585 IFP: 125-287:30" ISIP: 1174:60" BHT: 121F

FHP: 1569 FFP: 344-481:60" FSIP: 1174:90"

DST #2 (3361-3395) SIMPSON SAND

1) WB 2" in Bucket 2) WB 1 3/4" in Bucket

REC: 150' GIP

150' SG&OSM (Less than 1% Oil)

IHP: 2130 IFP: 54-39:30" ISIP: 185:60" BHT: 117F

FHP: 2095 FFP: 74-53:30" FSIP: 179:60"

DST #3 (3437-3447) ARBUCKLE

1) SBOB in 4 mins. 2) WBOB in 14 mins.

REC: 1020' GIP

180' CGO (25%G, 75%O)

180' CGO (30%G, 70%O)

210' CGO (20%G, 80%O)

120' SM&WGO (22%G, 52%O, 15%M, 11%W)

60' SM&WGO (12%G, 52%O, 18%M, 18%W)

60' G&OCWM (15%G, 20%O, 35%M, 30%W)

180' SG&OCWM (2%G, 2%O, 18%M, 78%W)

930' Total Fluid

IHP: 1710 IFP: 125-258:30" ISIP: 899:60" BHT: 119F

FHP: 1673 FFP: 332-433:60" FSIP: 887:90"

DST #4 (3448-3457) ARBUCKLE

1) SBOB in 1 min. 2) SBOB in 1 min.

REC: 2150' Wtr w/TO on Top

IHP: 1789 IFP: 294-606:30" ISIP: 1013:60" BHT: 121F

FHP: 1638 FFP: 737-928:60" FSIP: 1040:90"